

**SECTION 311000
SITE CLEARING**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Clearing and protection of vegetation.
- B. Removal of existing site improvements including existing sod and root zone material or other site improvements.

1.02 RELATED REQUIREMENTS

- A. Section 015713 - Temporary Erosion and Sediment Control.

PART 2 PRODUCTS

2.01 MATERIALS

- A. Fill Material: Section 329117 - Athletic Field Natural Grass Root Zone

PART 3 EXECUTION

3.01 SITE CLEARING

- A. Minimize production of dust due to clearing operations; do not use water if that will result in ice, flooding, sedimentation of public waterways or storm sewers, or other pollution.

3.02 EXISTING UTILITIES AND BUILT ELEMENTS

- A. Coordinate work with University and utility companies; notify before starting work and comply with their requirements; obtain required permits.
- B. Protect existing utilities to remain from damage.
- C. Do not disrupt University or public utilities without permit from authority having jurisdiction.
- D. Protect existing structures and other elements that are not to be removed.
- E. Pavements and slabs are to be saw cut to provide a clean edge. Concrete pavements are to be cut at the nearest control joint to the required demolition area.

3.03 VEGETATION

- A. Scope: Remove sod and root zone material as required for new work and as described in these contract documents.
- B. Vegetation Removed: Do not burn, bury, landfill, or leave on site, except as indicated.
 - 1. Sod: Remove from site; sell if marketable, and if not, treat as specified for other vegetation removed.
- C. Restoration: If vegetation outside removal limits or within specified protective fences is damaged or destroyed due to subsequent construction operations, replace at no cost to Owner.

3.04 DEBRIS

- A. Remove debris, junk, and trash from site.
- B. Leave site in clean condition, ready for subsequent work.
- C. Clean up spillage and wind-blown debris from public and private lands.

END OF SECTION