



NOTES:
1.) THE BOTTOM 12 INCHES OF THE FABRIC SHALL BE BURIED IN A 6" TRENCH CUT INTO THE GROUND COVERED BY 6" OF FILL MATERIAL TO PREVENT SEDIMENT FROM ESCAPING UNDER THE FENCE. ALL EARTHWORK SHALL BE ON THE UPSTREAM SIDE OF THE FENCE.

GENERAL SITE NOTES

1. THE SITE PLANS WERE PREPARED BASED UPON TOPOGRAPHIC SURVEYS BY ENDRS ENGINEERING, P.C., 771 ENTERPRISE DRIVE, LEXINGTON, KY 40510. REFER TO SITE SURVEY SHEET AND DESIGN DRAWINGS DONE BY OTHERS.
2. CONTRACTOR TO VERIFY EXISTING ELEVATIONS PRIOR TO STARTING ANY WORK. ANY DISCREPANCIES FOUND ARE TO BE REPORTED TO THE ARCHITECT AND OWNER.
3. THE ARCHITECT AND ARCHITECT'S CONSULTANTS SHALL HAVE NO RESPONSIBILITY FOR THE DISCOVERY, PRESENCE, HANDLING, REMOVAL OR DISPOSAL OF, OR EXPOSURE OF PERSONS TO HAZARDOUS MATERIALS IN ANY FORM AT THE PROJECT SITE, INCLUDING BUT NOT LIMITED TO ASBESTOS, ASBESTOS PRODUCTS, POLYCHLORINATED BIPHENYL (PCB) OR OTHER TOXIC SUBSTANCES.
4. THE CONTRACTOR SHALL USE EXTREME CARE IN WORKING AROUND EXISTING OVERHEAD AND UNDERGROUND UTILITIES. MEASURES SHOULD BE TAKEN TO PROTECT ALL UTILITIES FROM DAMAGE DURING CONSTRUCTION.

SITE DEMOLITION TAGS

- ◊ EXISTING TO REMAIN. PROTECT THROUGHOUT CONSTRUCTION.
- ◊ BLEACHERS TO REMAIN. STANDS ARE NOT ACCURATE TO EXISTING CONDITIONS.
- ◊ PAVEMENT TO REMAIN- PATCH/REPAIR WHERE DAMAGED BY CONSTRUCTION. SAW-CUT TO PROVIDE CLEAN EDGE. CONCRETE PAVING TO BE SAW-CUT BACK TO NEAREST UNMATERIALIZED CONTROL OR ISOLATION JOINT. MATCH NEW ADJACENT PAVEMENT TO EXISTING PAVEMENT ELEVATIONS.
- ◊ TREE/VEGETATION TO REMAIN.
- ◊ UTILITY TO REMAIN.
- ◊ FENCING TO REMAIN.
- ◊ STORM LINE/STRUCTURE TO REMAIN
- ◊ GRASS TO REMAIN.
- ◊ TURF SECTION TO REMAIN.
- ◊ REMOVE SOD AND ROOT ZONE MATERIAL TO A DEPTH OF 8-INCHES OR A DEPTH 2.5-INCHES BELOW NEW FINISHED GRADE, WHICHEVER IS DEEPER.
- ◊ IRRIGATION CONTROL VALVES AND HEADS TO BE ADJUSTED TO NEW GRADES.

SITE BMP NOTES

1. CONTRACTOR IS TO PROVIDE ALL KPDES PERMITS, NOTICES OF INTENT (NOIS) AND NOTICES OF TERMINATION INCLUDING EROSION AND SEDIMENT CONTROL PLANS FOR ALL PHASES OF CONSTRUCTION. ALL KPDES AND RELATED DIVISION OF WATER REQUIREMENTS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR UNTIL THE PROJECT IS CLOSED OUT AND THE NOTICE OF TERMINATION APPROVED.
2. SEDIMENT CONTROL FENCING SHOWN AND REFERENCES TO SEDIMENT CONTROLS AT STORM WATER STRUCTURES AND ELSEWHERE ON THE DOCUMENTS ARE NOT TO BE USED FOR DIVISION OF WATER REQUIREMENTS. THESE REFERENCES ARE ONLY REQUIRED BY THE DESIGNER FOR PROPER MAINTENANCE OF THE STORM WATER SYSTEM AND TO MINIMIZE CLEANING OF THE SYSTEM AND PAVEMENTS.
3. EXISTING VEGETATION IS TO BE LEFT INTACT UNTIL CONSTRUCTION IN THAT PARTICULAR LOCATION IS REQUIRED. SOIL STABILIZATION PRACTICES (SEEDING, MULCHING, ETC.) ARE TO BEGIN WITHIN 14 DAYS OF FERMANTMENT COMPLETION OR TEMPORARY HALT (21 DAYS OR MORE) OF WORK IN ANY PARTICULAR AREA.
4. PERIMETER SEDIMENT AND EROSION CONTROLS ARE TO BE INSTALLED PRIOR TO THE START OF SITE CLEARING AND GRUBBING. SILT FENCE SHALL BE INSTALLED TO PREVENT EROSION AND WASH-OFF ONTO WALKS, PAVEMENTS AND ALL ADJOINING PROPERTIES.
5. INSTALL SEDIMENT CONTROL FENCE AROUND ALL STORM WATER INLETS AND MAINTAIN UNTIL VEGETATION IS ESTABLISHED OR AREA PAVED AS APPROVED BY THE ARCHITECT. REMOVE PROTECTIONS AT THE COMPLETION OF THE PROJECT WHEN CONDITIONS NO LONGER WARRANT THEIR USE.
6. SEDIMENT CONTROLS ARE TO BE INSPECTED, CLEANED AND REPAIRED AFTER EACH RAIN EVENT OF 0.5 INCHES OR MORE, BUT NO LESS THAN ONCE PER WEEK. A LOG OF INSPECTIONS AND CLEANING IS TO BE KEPT ON SITE.
7. THE LOCATIONS OF SEDIMENT CONTROLS SHOWN ARE FOR GENERAL PROTECTION PRACTICES AND NOT AS PART OF A BMP PLAN. IF CONSTRUCTION ACTIVITIES PRODUCE CONDITIONS THAT REQUIRE ADDITIONAL CONTROLS, IT IS THE CONTRACTORS RESPONSIBILITY TO PROVIDE, INSTALL, AND MAINTAIN THE CONTROLS UNTIL CONDITIONS NO LONGER WARRANT THEIR USE.
8. ALL STORM DRAINAGE CATCH BASINS, CURB INLETS, AND JUNCTIONS BOXES ARE TO RECEIVE PROTECTION FROM SEDIMENTATION. AT A MINIMUM A PERIMETER SILT FENCE SHOULD BE INSTALLED AROUND THE DRAINAGE STRUCTURE AND INSTALLED UNDER THE GRATE.

LEGEND

- ☒ REMOVE FIELD MATERIAL.
- CONSTRUCTION LIMITS.
- SEDIMENT CONTROL FENCE. ADDITIONAL FENCE MAY BE REQUIRED AT OTHER AREAS DURING CONSTRUCTION. SEE DETAIL B/SDO.1.
- ◻ INLET PROTECTION. SEE DETAIL B/SDO.1

NOT FOR CONSTRUCTION

SITE DEMOLITION AND EPSC PLAN
FOR:
UK SOCCER FIELD UPGRADE
UNIVERSITY OF KENTUCKY
LEXINGTON, KENTUCKY

UK# A2310400
ASSIGNMENT# 24-1

Project No: 23064
Drawn By: SAS/ELM
Rev'd By: LMR

1	SHEET RELEASE
2	
3	
4	
5	
6	
7	
8	

COPYRIGHT © 2024
CONSTRUCTION DOCUMENTS

SDO.1
SITE DEMOLITION AND EPSC PLAN
DATE ISSUED: 1/5/24

SITE DEMOLITION AND EPSC PLAN
SCALE: 1"=20'

