

Procurement Services

INVITATION FOR BIDS CCK-2761.0-1-24 Cooling Plant #1 - Foam Roof ADDENDUM # 1 3/4/2024

IMPORTANT: BID AND ADDENDUM MUST BE RECEIVED BY 3/15/2024 @ 3:00 P.M. LEXINGTON, KY TIME

Bidder must acknowledge receipt of this and any addendum as stated in the Invitation for Bids.

ITEM #1: BIDDER NOTICES

- This addendum extends the question deadline to 3/5/2024.
- Please refer to and incorporate within the offer the attached revised specifications.

OFFICIAL APPROVAL UNIVERSITY OF KENTUCKY

Patricia Pfl

Contracting Officer / 859-257-9100

SIGNATURE

Typed or Printed Name

University of Kentucky Purchasing Division 322 Peterson Service Building Lexington, KY 40506-0005

An Equal Opportunity University

5.2 SPFR Roof Application (Revised 3/1/2024)

- A. The scope of work should include but is not limited to the following nor does it provide sequencing.
 - 1. Remove the existing Modified Bitumen roofing system to the deck including all wall flashing.
 - 2. Remove the existing parapet and perimeter sheet metal coping.
 - 3. Remove all asphaltic flashing membrane
 - 4. Remove and store the lightning protection that interferes with the roofing project.
 - 5. Remove and dispose of identified unused equipment and other identified appurtenances.
 - 6. Remove and discard specified electric conduit, wiring, and light fixtures.
 - 7. Mechanically attach new prefinished 24-gauge steel foam-stop to top of parapet walls and roof perimeters submit color samples.
 - 8. Prepare the deck to receive the new tapered insulation system
 - 9. Install fully adhered taper insulation and ½" Densdeck cover board.
 - 10. Positive drainage must be accomplished as the roof remains shaded under the steel grating above i.e., no ponding water.
 - 11. Prepare existing metal counterflashing to receive the foam roof up and under the counterflashing.
 - 12. Install the specified SPFR roof system
 - 13. Refer to the drawing for additional details and work operations.
 - 14. Reinstall and have the lightning protection certified after the roofing installation has been completed.