

01000S01- Special Conditions - General Contractor

UNIVERSITY OF KENTUCKY
SPECIAL CONDITIONS OF THE CONTRACT
FOR CONSTRUCTION BY A GENERAL CONTRACTOR

TABLE OF CONTENTS

ARTICLE 02 FIELD CONDITIONS	2
ARTICLE 03 (NOT USED)	2
ARTICLE 04 CONSULTANT (NOT USED)	2
ARTICLE 05 GEOTECHNICAL REPORT (NOT USED)	2
ARTICLE 06 TIME FOR COMPLETION	2
ARTICLE 07 LIQUIDATED DAMAGES	2
ARTICLE 08 SUBMITTALS AND SHOP DRAWINGS	3
ARTICLE 09 PLANS, DRAWINGS, AND SPECIFICATIONS (NOTS USED)	8
ARTICLE 10 PROGRESS MEETINGS	8
ARTICLE 11 CONSTRUCTION SCHEDULE – BAR CHART	9
ARTICLE 12 WALK-THROUGH	12
ARTICLE 13 OWNER’S CONSTRUCTION REPRESENTATIVE (NOT USED)	12
ARTICLE 14 FIELD OFFICE (NOT USED)	12
ARTICLE 15 TELEPHONE SERVICE	12
ARTICLE 16 CONSTRUCTION FENCE (NOT USED)	12
ARTICLE 17 PROJECT SIGN (NOT USED)	12
ARTICLE 18 PARKING	12
ARTICLE 19 SANITARY FACILITIES	12
ARTICLE 20 RULES OF MEASUREMENT	13
ARTICLE 21 ALLOWANCES (NOTS USED)	13
ARTICLE 22 SEQUENCE OF CONSTRUCTION	13
ARTICLE 23 CRANE & MATERIAL HOIST OPERATIONS (NOT USED)	14
ARTICLE 24 UTILITIES	14
ARTICLE 25 CLEANING AND TRASH REMOVAL	14
ARTICLE 26 BLASTING (NOT USED)	15
ARTICLE 27 CUTTING AND PATCHING - NEW AND EXISTING WORK	15
ARTICLE 28 UNRELATED PROJECTS	15
ARTICLE 29 OWNER SUPPLIED MATERIALS (NOT USED)	15
ARTICLE 30 REMOVED ITEMS	15
ARTICLE 31 INTERIOR ENCLOSURE AND DUST ENCAPSULATION	15
ARTICLE 32 UK ITS COMMUNICATIONS AND NETWORK SYSTEMS	16
ARTICLE 33 EMERGENCY VEHICLE ACCESS	16
ARTICLE 34 SMOKE DETECTORS / FIRE ALARM SYSTEMS- EXISTING AND/OR NEW FACILITIES	17
ARTICLE 35 SURVEYS, RECORDS, AND REPORTS	17
ARTICLE 36 TOBACCO PRODUCTS PROHIBITED	18
ARTICLE 37 ALTERNATES	18
ARTICLE 38 FIELD CONSTRUCTED MOCKUPS (NOT USED)	18
ARTICLE 39 PROJECT COORDINATION VIA COMPUTER	18
ARTICLE 40 HOT WORK PERMITS	19
ARTICLE 41 INSURANCE	19
ARTICLE 42 KEY ACCESS	20
ARTICLE 43 CEILING CLEARANCE	20
ARTICLE 44 METAL ANCHORS	21
ARTICLE 45 CONTRACTOR/SUPERINTENDENT EXPERIENCE	21

010000S01- Special Conditions - General Contractor

ARTICLE 01 GENERAL INFORMATION

1.1 These Special Conditions are intended to modify, supplement, or delete from applicable Articles of the General Conditions.

1.2 Where any Article of the General Conditions is supplemented by these Special Conditions, the Article shall remain in effect and the supplement shall be added thereto.

1.3 Where Special Conditions conflict with General Conditions, provisions of the Special Conditions take precedence.

ARTICLE 02 FIELD CONDITIONS

2.1 General Contractor will secure all data at the site of the building such as grades of lot, convenience of receiving and sorting material, location of public services, and other information which will have a bearing proposal or on the execution of the Work and shall address these issues in the preparation of their bid. No allowance shall be made for failure of the General Contractor to obtain such site information prior to submitting their proposal, and no adjustment to the General Contractor's Contract amount or stipulated time for completion shall be allowed when due to failure by the General Contractor to do so.

ARTICLE 03 (NOT USED)

ARTICLE 04 CONSULTANT (NOT USED)

ARTICLE 05 GEOTECHNICAL REPORT (NOT USED)

ARTICLE 06 TIME FOR COMPLETION

6.1 The time for Substantial Completion as further defined in Article 1 of the General Conditions shall be one hundred twenty (120) consecutive calendar days from the date of commencement as specified in the Notice to Proceed, and Final Completion shall be thirty (30) consecutive calendar days thereafter.

ARTICLE 07 LIQUIDATED DAMAGES

7.1 Should the General Contractor fail to achieve Substantial Completion of the Work under this Contract on or before the date stipulated for Substantial Completion (or such later date as may result from extensions in the Contract Time granted by the Owner), he agrees that the Owner is entitled to, and shall pay the Owner as liquidated damages the sum of two hundred fifty dollars (\$250.00) for each consecutive calendar day that Substantial Completion has not been met. See Article 3 of the Agreement.

7.2 Should the General Contractor fail to achieve Final Completion of the Work under this Contract on or before the date stipulated for Final Completion (or such later date as may result from extensions in the Contract Time granted by the Owner), he agrees that the Owner is entitled to, and shall pay the Owner as liquidated damages the sum of one hundred dollars (\$100.00) for each consecutive calendar day until Final Completion is reached. See Article 3 of the Agreement.

01000S01- Special Conditions - General Contractor

ARTICLE 08 SUBMITTALS AND SHOP DRAWINGS

8.1 SUBMISSIONS - GENERAL

8.1.1 The General Contractor shall submit each set of Shop Drawings, product data, samples, and test and/or certification reports as a separate item in UK E-Communication®. Projects not utilizing UK E-Communication® must submit all items electronically to the Consultant and the UK Project Manager and Administrative Coordinator.

8.1.2 All sample selections for color shall be submitted for approval at the same time. Color selections shall not be submitted individually.

8.1.3 Any deviation from the Contract Documents shall be noted on the transmittal form comment section.

8.1.4 All submittals are to be reviewed by the General Contractor for compliance with the Contract Documents before submission for approval. All submittals are to be initiated by the General Contractor. Submittals made directly to the Consultant by sub-contractors, manufacturers or suppliers will not be accepted or reviewed.

8.1.5 Re-submittals shall conspicuously note all changes from earlier submissions. Special notation by the General Contractor shall be made to any changes other than those in response to the Consultant's review.

8.1.6 Manufacturers shall, when requested by the Consultant, submit test reports prepared by reputable firms or laboratories certifying as to performance, operation, construction, wearability, etc., to support claims made by the manufacturer of the equipment or materials proposed for inclusion in the Work. General Contractor shall also submit a list of three (3) installations where said equipment or materials have been in service for a minimum of five (5) years.

8.2 SUBMISSIONS - REVIEW

8.2.1 Review of submittals is only for compliance with the design concept and the contract documents. **THE CONSULTANT SHALL NOT BE RESPONSIBLE FOR CHECKING DEVIATIONS FROM CONTRACT DOCUMENT REQUIREMENTS OR CHANGES FROM EARLIER SUBMISSIONS NOT SPECIFICALLY NOTED.**

8.2.2 The following shall be verified prior to making submittals:

Field Measurements, Field Construction Criteria, Catalog numbers and similar data, Quantities and Capacities, and Compliance with requirements, including verification of all dimensions,

8.2.3 Review Stamp designations shall be as follows:

8.2.3.1 "NET = No Exceptions Taken": Proceed with the Work, no corrections needed.

8.2.3.2 "FC= Furnish as Corrected": Proceed with the Work, noting the corrections/conditions of the approval.

010000S01- Special Conditions - General Contractor

8.2.3.3 "RR = Revise and Resubmit": Do not proceed with the Work, as the submittal does not comply with the Contract Documents. Revisions to the submittal are required for approval. On projects utilizing UK E-Communication, "Send Back a Step" is used in lieu of "Revise and Resubmit."

8.2.3.4 "R = Rejected": Do not proceed with the Work, the submittal is rejected.

8.3 SUBMISSIONS - SPECIAL PROVISIONS

8.3.1 In making a submittal, the General Contractor shall be deemed to be making the following representations:

8.3.1.1 The General Contractor understands and agrees that he shall bear full responsibility for the products furnished. The General Contractor expressly warrants that products described in the attached submittal will be usable and that they conform to the Contract requirements unless specifically noted otherwise.

8.3.1.2 The General Contractor understands and agrees that, without assuming design responsibility, he expressly warrants that products described in the attached submittal are capable of being used in accordance with the intent of the design documents and that they conform to the Contract requirements unless specifically noted otherwise.

8.3.1.3 The General Contractor acknowledges that the Owner will rely on the skill, judgment, and integrity of the General Contractor as to conformance requirements and subsequent usability.

8.4 SHOP DRAWING AND PROCUREMENT SUBMITTAL LOG

8.4.1 The General Contractor, within ten (10) days after the Pre-Construction meeting, shall begin uploading submittals using UK E-Communication[®], to generate a log fixing the dates for submission of Shop Drawings, special order material items, certifications, guarantees, and any other items required to be submitted to the Consultant for review, approval or acceptance. Projects not utilizing UK E-Communication[®] will submit a Shop Drawing Log provided by the Owner during the Pre-Construction Meeting.

8.4.2 The log shall track all submittals to date. The updated log shall then be reviewed and discussed at each progress meeting to determine items that may impact the construction schedule.

8.5 Shop Drawings

8.5.1 The General Contractor shall review, approve, and submit Shop Drawings to the Consultant, in accordance with the Consultant's Shop Drawing & Procurement Submittal Log or UK E-Communication[®], as herein detailed. By approving and submitting Shop Drawings, the General Contractor represents that he has determined and verified all materials, field measurements, and field construction criteria related thereto, or will do so, and that he has checked and coordinated the information contained within such submittals with the requirements of the Work and of the Contract Documents.

010000S01- Special Conditions - General Contractor

8.5.2 The General Contractor shall submit Shop Drawings required for the Work and the Consultant will review and take appropriate action. The review and approval shall be only for conformance with the design concept of the Project and for compliance with the information given in the Contract Documents. The approval of a separate item will not indicate approval of the assembly in which the item functions.

8.5.3 The General Contractor shall make any corrections required by the Consultant for compliance with the Contract and shall return the required number of corrected copies of Shop Drawings and resubmit new samples until approved. The General Contractor shall direct specific attention, in writing, or on resubmitted Shop Drawings, to revisions other than the corrections called for by the Consultant on previous submissions. The General Contractor's stamp of approval on any shop drawing or sample shall constitute a representation to Owner and Design Consultant that the General Contractor has either determined and verified all quantities, dimensions, field construction criteria, materials, catalog numbers, and similar data, or he assumes full responsibility for doing so, and that he has reviewed or coordinated each shop drawing or sample with the requirements of the Work and the Contract Documents.

8.5.4 Where a shop drawing or sample submission is required by the specifications, no related Work shall be commenced until the submission has been approved by the Design Consultant. A copy of each approved shop drawing and each approved sample shall be kept in good order by the General Contractor at the site and shall be available to the Consultant.

8.5.5 The Consultant's approval of Shop Drawings or samples shall not relieve the General Contractor from his responsibility for any deviations from the requirements of the Contract Documents unless the General Contractor has in writing called the Consultant's attention to such deviation at the time of submission and the Consultant has given written approval to the specific deviation. Any approval by the Consultant shall not relieve the General Contractor of responsibility for errors or omissions in the Shop Drawings.

8.5.6 All submittals are to be submitted electronically by the contractor. Shop Drawings submitted through UK E-Communication® shall be scanned and submitted in color. Mark-ups must be made using visible color when printed. Workflow in UK E-Communication® will be established during the workflow meeting. Each individual Shop Drawing shall have its respective specification number and description highlighted.

8.5.7 Where Shop Drawings include fire alarm, communication systems schematics, sprinkler systems, etc., a sepia of each drawing shall be submitted to the Consultant as part of the "Record" set of drawings.

8.6 SUBMISSIONS - SAMPLES

8.6.1 Office samples shall be of sufficient size and quantity to clearly illustrate functional characteristics of the product with integrally related parts and attachment devices, and full range of color, texture, and pattern.

8.6.2 Products shall not be used until the sample has been submitted to and approved by the Consultant.

010000S01- Special Conditions - General Contractor

8.6.3 A minimum of two (2) samples are required to be submitted to the Consultant for review and approval and will be distributed as follows:

- a) One (1) to be retained by the University.
- b) One (1) to be returned to the Design Consultant.
- c) An additional sample or samples may be submitted, at the General Contractor's option, for distribution to a third party.

8.6.4 Field samples (block, brick, etc.) of materials to be constructed at the site shall be submitted for review as required by the individual section of the Contract Documents.

8.7 SUBMISSIONS - OPERATION AND MAINTENANCE MANUALS

8.7.1 The University requires a minimum of one (1) digital copy of the final installation, training, operation, maintenance, and repair manuals to be turned over to the Owner's Project Manager and approved for content by the Consultant by or before the time construction is 75% complete. Projects utilizing e-Communication will create digital copy from the Document Library (Closeouts) in e-Communication. Operation and maintenance manuals and materials, where specified, for mechanical and electrical equipment and for operating items other than mechanical and electrical equipment must be submitted in PDF format with a separate PDF file for each item. In the event the Construction Manager fails to provide these required electronic submittals prior to reaching seventy-five (75%) completion, it is agreed that the Owner at its sole discretion may deduct from the current and subsequent Applications for Payment an amount deemed by the Owner to be sufficient to encourage prompt compliance with this contractual requirement, until such time as acceptable O&M manuals are received.

8.7.2 Manuals provided must be of sufficient detail to enable the Owner or others to install, calibrate, train, operate, maintain, service and repair every system, subsystem, and/or piece of equipment installed on or as part of this Contract. Manuals submitted through UK E-Communication® shall be scanned and submitted in color. Mark-ups must be made using visible color when printed. Each manual must contain:

8.7.2.1 Project Title, Project number, Location, dates of submittals, names, addresses and phone number for the Consultant, Construction Manager, and Construction Manager's Subcontractors;

8.7.2.2 An Equipment Index that includes vendors' names, addresses, and telephone numbers for all equipment purchased on the Project.

8.7.2.3 Emergency instructions with phone numbers and names of contact persons on warranty items shall be uploaded to UK E-Communication®.

8.7.2.4 Copies of each system's air balancing record and each system's hydronic balancing record (1) digital copy in eCommunication.

8.7.2.5 Copy of valve tag list.

8.7.2.6 Copy of As-Built temperature control system drawings and components and sequence of operation.

01000S01- Special Conditions - General Contractor

8.7.2.7 Original copies of the following provided by the manufacturer:

Installation manuals	Instruction Manuals
Training manuals	Calibration manuals
Service Manual	Operation manuals
Parts list	Repair manuals
Reviewed Shop Drawings	Wire list
Keying Bit List	

8.7.2.8 Any Computer, Micro controller, and/or Microprocessor equipped equipment installed shall be provided with source code copies of all software and firmware (prom, eprom, rom, other) supplied on this Contract; and

8.7.2.9 Copies of all inspection and guarantee certificates, manufacturers' warranties with the University of Kentucky listed as the Owner for all equipment provided and/or installed.

8.7.2.10 Refer to the Official Design Standards 017800S01 – Closeout Submittals for full details <https://www.uky.edu/cpmd/download/file/fid/78986>

8.7.2.11 If the O&M manuals from any one vendor covering several different model numbers, the model used on the Project must be highlighted.

8.7.2.12 Included in the front of the "Operation and Maintenance Manual" shall be a copy of the Interior and Exterior Finish plan and Schedule listing all finish materials, the manufacturer, the finish color, and the manufacturer's paint number.

8.7.2.13 Photograph album containing photos and negatives or digital images (.pdf format) showing buried utilities and concealed items shall be included.

8.7.3 SUBMISSIONS – OWNER TRAINING VIDEOS

8.7.3.1 Owner training shall be provided for all new and modified electrical and mechanical systems. Video recordings shall be made for each training session. All training videos must be provided to UK Project Coordinator prior to Final Completion.

8.9 SUBMISSIONS – AS - BUILT SET OF DRAWINGS

8.9.1 The General Contractor shall submit one (1) electronic copy of As - Built set of drawings in .pdf format indicating all deviations of construction as originally specified in the Contract Documents. These As-Built Drawings will compile information from the General Contractor as well as all Sub-contractors. The General Contractor shall provide a qualified representative to update the As - Built set of drawings as construction progresses. As-Built submitted through UK E-Communication® shall be scanned and submitted in color. Mark-ups must be made using visible color when printed

8.9.2 The General Contractor shall provide and utilize a camera to photograph the installation of buried utilities and concealed items. The General Contractor shall provide standard 3 1/2" x 5" photographs with negatives, or digital images (.jpeg format), which shall be submitted as part of the Operation and Maintenance Manuals submission. These photos should be mounted in a bound album or stored on a new flash drive with labeling as to subject of photo, date, and Project. Such album or drive is to be kept at job site with the As - Built set of drawings until submittal of same.

01000S01- Special Conditions - General Contractor

8.9.3 Approval of the Final Payment request will be contingent upon compliance with these provisions. The General Contractor's As – Built set of drawings shall be delivered to the Consultant at their completion so that the Consultant may make any changes on the original contract drawings.

8.10 SUBMISSIONS - SAP EQUIPMENT LIST

8.10.1 Complete equipment list for use with SAP software in electronic spreadsheet format. Data is to be provided in Unifomat format with the information being provided for individual locations as noted in Attachment A – Unifomat Component List. Information is to be provided as follows (PPDMC or CPPD will provide blank Excel spreadsheets in electronic form for use in compiling the information, if desired)

8.10.2 All materials that require preventative maintenance (PM) are listed as in Attachment A. The equipment list is to be provided in Excel spreadsheet format and is to include the information listed in Attachment B

8.10.3 Required maintenance procedure listing each work task in Excel spreadsheet format as shown in Attachment C.

8.10.4 Required frequency of maintenance for the work tasks outlined in 8.9.3 above and included in the Attachment C spreadsheet

8.10.5 Listing of maintenance parts and items: i.e., filters, lubricants, etc. for each work task listed in 8.9.3 above.

8.11 SUBMISSIONS – MAINTENANCE MATERIALS

8.11.1 If specified, Maintenance/Replacement Materials, Spare Parts, and special maintenance tools for proper maintenance shall be provided by the General Contractor.

ARTICLE 09 PLANS, DRAWINGS, AND SPECIFICATIONS (Nots Used)

ARTICLE 10 PROGRESS MEETINGS

10.1 In addition to specific coordination and pre-installation meetings for each element of Work, and other regular Project meetings held for other purposes, progress meetings will be held as outlined at the Preconstruction Meeting. Each entity then involved in planning, coordination or performance of Work shall be properly represented at each progress meeting. The following areas will be covered at each progress meeting: current status of work in place, General Contractor's review of upcoming work (1 month look ahead), schedule status, upcoming outages, new outage requests, shop drawings due from contractors, shop drawings being reviewed, outstanding RFI's, outstanding proposed change orders, change orders, new business, As-Built updated, close-out documents status, defective work in place issues, review "pencil copy" of payment application, safety issues and new business or other issues not covered above. With regard to schedule status, discuss whether each element of current work is ahead of schedule, on time, or behind schedule in relation with updated progress schedule; determine how behind-schedule Work will be expedited, and secure commitments from entities involved in doing so; discuss whether schedule revisions are required to ensure that current Work and subsequent Work will be completed within Contract Time; and review everything of significance which could affect the progress of the Work.

010000S01- Special Conditions - General Contractor

10.2 General Contractor shall prepare and submit at each progress meeting an updated schedule indicating Work completed to date and any revisions needed.

10.3 With the express purpose of expediting construction and providing the opportunity for cooperation of affected parties, progress meetings will be held and attended by representatives of:

- (1) The Owner's Project Manager
- (2) The Consultant.
- (3) General Contractor.
- (4) Sub-contractors.
- (5) Others requested to attend (as deemed necessary by CPMD).
- (6) Physical Plant Division Representative

10.4 A location near the site will be designated where such progress meetings will be held. Participants will be notified of the dates and times of the meetings by the Consultant.

ARTICLE 11 CONSTRUCTION SCHEDULE – BAR CHART

11.1 The General Contractor shall prepare construction schedules as a bar chart, with separate divisions for each major portion of the work, and in sufficient detail to identify the plan and sequence of construction to be followed in meeting the requirements of the Contract. Schedules shall include divisions for Work to be accomplished remote from the central construction site, e.g., utilities from outside the construction site to the site for chilled water, steam, electrical, communications, and/or fire service. Such Work shall be scheduled so that disruption resulting from construction will be minimized. Start dates and completion dates for such Work must be maintained and completed in the shortest reasonable time. The sequence of listings shall follow the Table of Contents of the Specifications. Maximum sheet size shall be 30" x 42". The schedule shall show the complete sequence of construction, by activity, with dates for beginning and completion of each element of the Work.

11.1.1 For projects requiring a bar chart schedule instead of a Critical Path Method (CPM) schedule, the following Articles of the General Conditions are amended as follows:

11.1.2 Article 21.4.2 of the General Conditions to the Contract is amended to read as follows:

21.4.2 Requests for an extension of time due to unusually bad weather shall be considered for approval only if it is shown that a) the unusual weather event delayed work on a specific weather sensitive activity or activities that had been planned to be underway on the date(s) on which the weather event occurred, as shown in the most recent update to the Project schedule that had been submitted to the Owner prior to the date of the event and b) that the delay to that activity or activities is shown to be the proximate cause of a corresponding delay to the contractually required completion dates for the Project that were shown in the most recent update to the Project schedule. The actual dates on which the delay(s) occurred must be stated and the specific activities that were directly impacted must be identified. In the event of concurrent delays, only those activities actually impacting the Project contractually required completion dates will be considered in evaluating the merit of a delay request and in adjusting the schedule. Time extensions will not be considered for concurrent delays not caused by the Owner. Requests for an extension of time which are not supported by this information shall not be considered for approval by the Owner.

010000S01- Special Conditions - General Contractor

11.1.3 Article 21.4.3 of the General Conditions to the Contract is amended to read as follows:

21.4.3 In anticipation of the possibility of delay due to unusual bad weather, the General Contractor shall identify those activities in the schedules, and those activities subsequently added to updated schedules, that might reasonably be expected to be delayed by bad weather.

11.1.4 Article 21.7 of the General Conditions to the Contract is amended to read as follows:

21.7 The Contract Time will only be adjusted for causes specified above. Extensions of time will only be approved if the General Contractor can provide justification supported by the Project schedule or other acceptable data that such changes extend the contractually required date of Substantial Completion, and that the General Contractor has expended all reasonable effort to minimize the impact of such changes on the construction schedule. No additional extension of time will be granted subsequently for claims having the basis in previously approved extensions of time.

11.1.5 Article 21.8 of the General Conditions to the Contract is amended to read as follows:

21.8 In support of requests for an extension of time not caused by unusual inclement weather, and concurrently with the submittal of any such request, the General Contractor shall submit to the Consultant and the Owner a written impact analysis showing the influence of each such event on contractually required completion dates as shown in the updated Project schedule most recently submitted to the Owner prior to the event. The analysis shall include the sequence of new or revised activities and/or durations that are proposed to be added to the existing schedule including related logic. This impact analysis shall include the new activities and/or activity revisions proposed to be added to the existing schedule and shall demonstrate the claimed impact on the contractually required completion dates. The General Contractor will not be granted an extension of time and/or relief from liquidated damages when the delay to completion of the work is attributable to, within the control of, or due to the fault, negligence, acts, or omissions of the General Contractor and/or the General Contractor's contractors, subcontractors, suppliers, or their respective employees and agents. Time extensions will not be considered for concurrent delays not caused by the Owner. In the event of concurrent delays, only that event actually impacting contractually required completion dates will be considered in adjusting the schedule and evaluating the merit of a delay claim. Requests for an extension of time which are not supported by this information shall not be considered for approval.

11.1.6 Article 32.1 of the General Conditions to the Contract is amended to read as follows:

32.1 The General Contractor shall prepare and submit to the Owner and the Consultant a bar-chart type construction schedule for the Work. The schedules shall include all activities necessary for performance of the work showing the duration and the planned start and finish dates for each activity. The schedules shall include, but not be limited to, submittal processing, fabrication and delivery of materials, construction, testing, clean-up, work and/or materials to be provided by the Owner, dates and durations for major utility outages requiring coordination with the Owner and the Owner's operations, and significant milestones related to the completion of the Project.

010000S01- Special Conditions - General Contractor

11.2 The schedule shall be submitted to the Consultant and to the Owner for review within thirty (30) calendar days after the date established for the start of Work on the Project as stated in the official Work Order and Notice to Proceed. Review will be only for general conformance to the requirements of the contract. Review comments and/or acceptance of the Contractor's schedule shall not relieve the Contractor of any obligation for compliance with all requirements of the Contract Documents. Such review and comments shall not constitute interference with the Contractor's means and methods of construction, which shall remain solely the responsibility of the Contractor.

11.3 Schedules shall be revised no less frequently than monthly to coincide with regular monthly Project progress meetings and submission of Applications for Payment and shall be updated to indicate progress of each activity to the date of submittal, the projected completion of each activity, any activities modified since previous submittal, any major changes in scope, and all other identifiable changes, and further shall be accompanied by a narrative report to define problem areas, anticipated delays, impact on the progress of the Work, and to report corrective action taken or proposed.

11.4 Initial schedules shall be submitted within thirty (30) calendar days after the date established in Notice to Proceed. After review, required revisions to the schedule shall be completed and incorporated in the schedule within ten (10) calendar days. Up-dated Progress Schedules shall be submitted with each Application for Payment. Submissions must include one (1) opaque reproduction and one (1) electronic copy (disk or CD) along with a transmittal letter.

11.5 Copies of reviewed Schedules are to be provided to the job site file and, as appropriate, to sub-contractors, suppliers, and other concerned entities, including separate contractors. Recipients are to be instructed to promptly report, in writing, problems anticipated by projections shown in schedules.

11.6 The processing of all progress payments is contingent upon the submission of updated schedules.

11.7 The processing of all Change Orders requesting a time extension to the contract is contingent upon the submission and approval of a revised schedule demonstrating that the change order does impact the date of completion for the entire project. Time extension requests associated with Change Orders that do not impact the date of completion for the entire project will be rejected.

01000S01- Special Conditions - General Contractor

ARTICLE 12 WALK-THROUGH

12.1 After the "Work Order" is issued but before Work by the General Contractor is started, a walk-through of the area is required to document the condition of the space, surfaces, or equipment. It is the responsibility of the General Contractor to schedule the walk-through with the Owner's Project Manager, the Consultant, and other interested parties.

12.2 During the walk-through, General Contractor shall identify all damaged surfaces or other defective items that exist prior to construction.

12.3 The walk-through shall be attended by Owner's Project Manager, a Representative of the user of the facility, the General Contractor, and the Consultant

12.4 Written documentation of the walk-through is to be provided by the Consultant with copies distributed to all parties. Polaroid type color photographs are to be provided and labeled by General Contractor and one (1) copy of such photographs are to be given to Consultant. (Digital photos in a .jpg format are acceptable if submitted on digital media storage) All parties attending the walk-through agree on the list of damages.

ARTICLE 13 OWNER'S CONSTRUCTION REPRESENTATIVE (Not Used)

ARTICLE 14 FIELD OFFICE (Not Used)

ARTICLE 15 TELEPHONE SERVICE

15.1 General Contractor shall arrange through UK ITS Communications and Network Systems for installation of on-site phone, internet and other communications services. Telephone service during the length of construction shall be paid for by the General Contractor. (Cell phone/Nextel service in lieu of UK ITS Communications and Network Systems phone service may be utilized at General Contractor's option.)

ARTICLE 16 CONSTRUCTION FENCE (Not Used)

ARTICLE 17 PROJECT SIGN (Not Used)

ARTICLE 18 PARKING

18.1 There will be parking available at no cost to the awarded contractor.

ARTICLE 19 SANITARY FACILITIES

19.1 Restroom facilities in one of the surrounding buildings will be designated at the Pre-Construction Meeting for use by the General Contractor's workforce during construction. The designated restroom(s) and areas accessible to General Contractor must be kept clean and neat during construction. Failure to keep them clean will result in the General Contractor being required to provide portable toilets at his cost at the site. Drinking water shall be provided from an approved safe source so piped or transported as to be kept clean and fresh and served from single service containers or satisfactory types of sanitary drinking stands or fountains. All such facilities and services shall be furnished in strict accordance with existing governing health regulations.

01000S01- Special Conditions - General Contractor

ARTICLE 20 RULES OF MEASUREMENT

20.1 Rules of Measurement shall be established by the Consultant in the field. Actual measurement shall be taken in the field. These amounts shall become binding upon the General Contractor and be adjusted as before mentioned.

20.2 The General Contractor shall pay for and coordinate through the Consultant and/or the Owner's Project Manager all associated Work by utility companies including relocation of utility poles, installation of new streetlights, relocation of overhead or underground lines, and any other Work called for on the Plans and in the Specifications.

ARTICLE 21 ALLOWANCES (Nots Used)

ARTICLE 22 SEQUENCE OF CONSTRUCTION

22.1 **Not Used**

22.2 All materials and equipment are to be brought into the project site from the approved staging location and are not to be brought through the existing buildings or loading docks. Any and **all** exceptions shall be approved by, and closely coordinated with, the Owner's Project Manager in advance of scheduling or performing the work.

22.2.1 The General Contractor shall coordinate any road and sidewalk closings, utility disruptions, etc. which will affect the use of the existing building(s) with the Owner's Project Manager prior to commencing that Work.

22.3 The adjacent buildings and public areas will remain in use and the Owner shall have access to the existing building(s) throughout the duration of the Project. The General Contractor shall coordinate construction activity to assure the safety of those who must cross the Project site and shall provide and maintain the necessary barriers and accommodations for a completely safe route of accessibility. The General Contractor is to ensure that all exits provide for free and unobstructed egress. If exits must be blocked, prior arrangements must be made with the Owner's Project Manager.

22.4 The General Contractor shall cooperate with the Owner to minimize inconvenience to, or interference with normal use of existing buildings and grounds by staff, students, other Contractors, or the public. General Contractor shall conduct operations to prevent damage to adjacent building structures and other facilities and in such a manner to protect the safety of building's occupants.

22.5 Special effort shall be made by the General Contractor to prevent any employee from entering existing buildings for reasons except construction business. In particular, use of toilets, drinking fountains, vending machines, etc. is strictly prohibited.

010000S01- Special Conditions - General Contractor

ARTICLE 23 CRANE & MATERIAL HOIST OPERATIONS (Not Used)

ARTICLE 24 UTILITIES

ARTICLE 25 CLEANING AND TRASH REMOVAL

25.1 The General Contractor shall keep clean the entire area of new construction and shall keep streets used as access to and from the site free of mud and debris.

25.2 All exit ways, walks, drives, grass areas, and landscaping must be kept free from debris, materials, tools, and vehicles at all times. Trim weeds and grass within the site area.

25.3 Upon completion of the Work, General Contractor shall thoroughly clean and re-sod grass areas damaged to match existing areas.

26.4 All utility markings are to be made with water-based marking paint with low Volatile Organic Compounds (VOC's) and high solids.

26.5 Upon Completion of the project, buried utility paint markings sprayed on walks and hardscapes are to be removed by non-destructive means such as pressure washing. Do not use chemicals. If a washed area is noticeable, the entire surface must be washed and or blended to match surrounding areas.

25.6 The General Contractor shall be responsible for removal from the site of all liquid waste or other waste (i.e., hazardous, toxic, etc.) that requires special handling on a daily basis.

25.7 Dumpsters will be provided and maintained by the General Contractor.

25.8 During Work at the Project site, the General Contractor shall clean and protect Work in progress and adjoining Work on a continuing basis. General Contractor shall apply suitable protective covering on newly installed Work where needed to prevent damage or deterioration until the time of Substantial Completion. General Contractor shall clean and perform maintenance on newly installed Work as frequently as necessary through remainder of construction period.

25.9 The General Contractor shall be responsible for daily cleaning of spillage's and debris resulting from his and his Sub-contractor's operations, (includes removal of dust and debris from wall cavities), and for providing closed, tight fitting (dustproof if required), waste receptacles to transport construction debris from the work area to the dumpster. Broom clean all floors no less than once a week. The General Contractor shall empty such receptacles into the trash container when full or when directed to be emptied by the Consultant and/or Owner's Project Manager, but not less than weekly. The use of hospital waste and trash receptacles is strictly prohibited, except as otherwise provided by the project specifications.

25.10 Failure to comply with the above requirements shall be cause of stopping work until the condition is corrected.

010000S01- Special Conditions - General Contractor

ARTICLE 26 BLASTING (Not Used)

ARTICLE 27 CUTTING AND PATCHING - NEW AND EXISTING WORK

27.1 New Work - Cutting and patching shall be done by craftsmen skilled and experienced in the trade or craft that installed or furnished the original Work. Repairs shall be equal in quality and appearance to similar adjacent Work and shall not be obviously apparent as a patch or repair. Work that cannot be satisfactorily repaired shall be removed and replaced.

27.2 Existing Construction - Refer to Architectural, Mechanical, and Electrical drawings for cutting and patching. All new Work shall be connected to the existing construction in a neat and workmanlike manner, presenting a minimum of contrast between old and new Work. Do all patching of the existing construction as may be required for the new construction to be done. Necessary patching, closing of existing openings, repairing, and touching up shall be included as required for a proper, neat, and workmanlike finished appearance. Any existing item that is to remain and is damaged during construction shall be replaced at the General Contractor's expense.

ARTICLE 28 UNRELATED PROJECTS

28.1 Unrelated construction Projects may be under way in the vicinity of this Project or the site utility work during the course of the Work related to this Project. The General Contractor for this Project must coordinate with any other contractors regarding overlapping areas. See Article 42 - Separate Contracts of the General Conditions.

ARTICLE 29 OWNER SUPPLIED MATERIALS (Not Used)

ARTICLE 30 REMOVED ITEMS

30.1 The contractor will be required to remove all materials from the pneumatic system that is in place currently.

ARTICLE 31 INTERIOR ENCLOSURE AND DUST ENCAPSULATION

31.1 Areas under construction or renovation shall be separated from occupied areas by suitable temporary enclosures furnished, erected, and maintained by the General Contractor. Temporary enclosures shall be dust and smoke tight and constructed of non-combustible materials to prohibit dirt and air borne dust from entering occupied spaces. General Contractor to review with Consultant ways to provide ventilation for dust generated by demolition and fumes/vapors produced during installation of new materials.

31.2 General Contractor is responsible for coordinating with the Owner's Project Manager any equipment to be turned off prior to erecting temporary enclosures.

31.3 General Contractor shall protect all exhaust diffusers, equipment, and electrical devices from the collection of dust. All areas shall be checked and cleaned prior to final acceptance of Work.

31.4 Dust and debris from Work operations shall be held to a minimum.

010000S01- Special Conditions - General Contractor

31.5 General Contractor shall construct temporary dust partitions at locations and as detailed on drawings. Closures used for dust barricade shall be constructed of non-combustible materials, (metal studs and gypsum board or fire-retardant plywood).

31.6 General Contractor shall provide additional devices and materials required to contain dust within Work area and protect personnel during course of Work.

31.7 Areas of minor renovation, consisting of the removal of doors and frames, blocking of openings, and other limited Work shall be separated by a dust partition of fire retarded polyethylene on studs.

31.8 Existing corridor doors may serve as dust barriers, except if removed for refinishing. In such cases, temporary wood doors must be substituted until original doors are replaced.

31.9 The General Contractor may assume existing walls which extend full height, floor to structure, shall be deemed appropriate to contain airborne dust. Cover any voids or penetrations.

31.10 Doors or windows in the perimeter walls surrounding the Project work area shall be sealed off with protective materials in a manner to prohibit dust from escaping the work area. These shall be left in place until all work creating dust is completed. Protective materials shall consist of fire-retardant wood, metal studs, gypsum board or flame-resistant plastic.

31.11 Entry passage to Work area shall be sealed off with zippered plastic opening or other acceptable means which allows periodic entry and closure of barricade closure.

31.12 Install and maintain a “sticky mat” on the floor in locations where construction crews leave the construction area and prior to entering ANY existing space in the building.

31.13 Install and maintain a temporary floor covering in any and all elevators being utilized for this project.

ARTICLE 32 UK ITS COMMUNICATIONS AND NETWORK SYSTEMS

32.1 The University of Kentucky owns the campus Telephone system and the UK IT Communications and Network Systems is responsible for communications pre-wiring in all new and renovated facilities on the campus. The General Contractor, during the initial start-up of construction, shall coordinate with a representative from UK ITS Communications and Network Systems a time window as to when pre-wiring by University personnel for the phone system can start and when it must be finished prior to the installation of the finished ceiling. (Typically, same time frame as electricians installing wire.) Thirty (30) days’ notice shall be given to UK ITS Communications and Network Systems prior to the start of the time window for pre-wiring.

ARTICLE 33 EMERGENCY VEHICLE ACCESS

33.1 Emergency Vehicle Access must be maintained during construction. The General Contractor shall coordinate with the local Fire and Emergency Medical Services department(s) that would respond to an emergency during the initial start-up of construction to ensure a complete understanding of their requirements.

010000S01- Special Conditions - General Contractor

ARTICLE 34 SMOKE DETECTORS / FIRE ALARM SYSTEMS- EXISTING AND/OR NEW FACILITIES

34.1 General Contractor shall protect all smoke detectors in Work areas to prevent false alarms. The General Contractor will be responsible for any false alarm caused by dust created in their Work areas or dust traveling to areas beyond the Work past inadequate protection barriers. If there is a need for an existing or newly installed fire alarm system or parts of that system to be serviced, turned off, or disconnected, prior approval must be obtained from the Owner's Project Manager and notification given to the Campus Dispatch Office. The General Contractor must follow the procedure outlined for Utility Outages and any documented costs charged by the responding fire department due to a false alarm shall be paid by the General Contractor. As soon as all Work is completed, notification must be given to the Owner's Project Manager and to the Campus Dispatch Office prior to reactivation of the system. Prior to Final Payment to the General Contractor, all protected smoke detectors will be uncovered and tested.

34.1.1 When the function of any fire alarm, detection or suppression system is impaired, a temporary system shall be provided. General Contractor shall provide daily reports indicating the Superintendent has walked through the project at the end of each work period, to satisfy himself there are no present conditions that may result in an accidental fire. Portable fire extinguishers shall be on site during this time. The General Contractor is responsible for inspecting and testing any temporary systems on a monthly basis.

ARTICLE 35 SURVEYS, RECORDS, and REPORTS

35.1 General: Working from lines and levels established by property survey, and as shown in relation to the Work, the General Contractor will establish and maintain bench marks and other dependable markers to set lines and levels for Work at each area of construction and elsewhere on site as needed to properly locate each element of the entire Project. The General Contractor shall calculate and measure from the benchmarks and dependable markers required dimensions as shown (within recognized tolerances if not otherwise indicated) and shall not scale drawings to determine dimensions. General Contractor shall advise Sub-contractors performing Work of marked lines and levels provided for their use in layout of Work.

35.2 Survey Procedures: The General Contractor shall verify layout information shown on drawings, as required for his own Work. As Work proceeds, surveyor shall check every major element for line, level, and plumb (as applicable), and maintain an accurate Surveyor's log or Record Book of such checks available for General Contractor or Design Consultant's reference at reasonable times. Surveyor shall record deviations from required lines and levels, and advise Design Consultant or General Contractor promptly upon detection of deviations exceeding indicated or recognized tolerances. The General Contractor shall record deviations which are accepted (not corrected) on Record Drawings.

01000S01- Special Conditions - General Contractor

ARTICLE 36 TOBACCO PRODUCTS PROHIBITED

36.1 For areas located within Fayette County, Kentucky, the use of all tobacco products is prohibited on all property that is owned, operated, leased, occupied, or controlled by the University. "Property" for purposes of this paragraph includes buildings and structures, grounds, parking structures, enclosed bridges and walkways, sidewalks, parking lots, and vehicles, as well as personal vehicles in these areas. To view the Lexington campus boundaries: <http://www.uky.edu/TobaccoFree/files/map.pdf>.

36.2 For areas not located within Fayette County, Kentucky, smoking is prohibited in all owned, operated, leased, or controlled University buildings and structures, parking structures, enclosed bridges and walkways, and vehicles. Smoking is also prohibited outside buildings and structures within 20 feet of entrances, exits, air intakes, and windows, unless further restricted by division policy.

36.3 General Contractor employees violating this prohibition will be subject to dismissal from the Project.

36.4 For the full Administrative Regulation see University AR 6:5. <http://www.uky.edu/Regs/files/ar/ar6-5.pdf>

ARTICLE 37 ALTERNATES

37.1 Alternate(s) will be accepted in the sequence of the Alternates listed on the Bid Form, and the lowest Bid Sum will be computed on the basis of the sum of the base Bid and any alternates accepted, within the budgeted amount.

37.2 Schedule of Alternates:

1. Please submit an add alternate price to furnish and install the pneumatic tube from the location capped at the end of the current system and extending to the 4th and 5th floor.

ARTICLE 38 FIELD CONSTRUCTED MOCKUPS (Not Used)

ARTICLE 39 PROJECT COORDINATION VIA COMPUTER

39.1 The General Contractor and subcontractors are required to have an active email account to facilitate coordination of the project during construction and warranty.

39.2 To facilitate project construction coordination between the Consultant, the General Contractor, Subcontractors, and the University of Kentucky as the Owner, UK Capital Project Management Division (CPMD) is hosting an Internet/ Web-based Project Management System (WPMS) to help improve project communication and collaboration. The Consultant shall participate in the use of the WPMS (UK E-Communication® or other system at the Owner's discretion) providing collaboration between Owner, the Consultant, and selected contractors.

39.2.1 Owner shall provide the General Contractor and subcontractors with user accounts and appropriate training for the web-based project management tool.

01000S01- Special Conditions - General Contractor

39.2.2 Utilization of, and training in the use of, the WPMS will be arranged for and supervised by Owner.

39.2.3 Participation of General Contractor is mandatory; others as determined by Owner. Participation of Subcontractors is not mandatory but will be offered at their discretion.

39.2.4 All participants are required to have access to the internet and the Microsoft Internet Explorer browser (version 5.0 or higher). A broadband connection to the internet (e.g., Cable modem, ISDN, DSL) is recommended, but not required.

39.2.5 The WPMS shall be utilized for the following functions, as a minimum: Posting Project Files, AE Amendments, Architect's Supplemental Information (ASI's), Closeouts, Consultant Invoices, Contracts, Defective Work in Place, Meeting Minutes, Payment Applications, Proposed Change Orders – Change Orders (PCO to CO's), Punch Lists, Reports (Contractor Daily Reports, Field Reports, Commissioning Reports), RFIs, SAP Equipment List, Schedules, and Submittals. The Document Library (Bid set Plans, Specifications and Addenda will be uploaded by Lynn Imaging.

39.2.6 Site camera monitors may be included at Owner's discretion.

39.2.7 Utilization of the WPMS shall be implemented by the Owner's representative.

39.2.8 Use of the system will provide consistent, real-time information for decision making. Additionally, all project data entered into the system will be archived to facilitate project record keeping. It is anticipated that proper use of the WPMS will improve efficiency of communications and reduce project related paperwork and clerical workload.

ARTICLE 40 HOT WORK PERMITS

40.1 All work involving open flames or producing heat and/or sparks in occupied buildings on the University of Kentucky campus will require the General Contractor to obtain approval to perform "Hot Work" on site. This includes, but is not limited to: Brazing, Cutting, Grinding, Soldering, Thawing Pipe, Torch Applied Roofing, and Cadwelding. A copy of the Hot Work Permit and the Hot Work Permit Procedure will be passed out at the Preconstruction Conference for the General Contractor's use.

ARTICLE 41 INSURANCE

41.1 Employers' Liability Insurance. The General Contractor shall acquire and maintain Employers' Liability insurance with at least \$500,000/\$500,000/\$500,000 limits of liability for all employees who will be working at the Project site.

41.2.1 Commercial General Liability Insurance. If the work involved requires the use of helicopters, a separate aviation liability policy with limits of liability of \$100,000,000 will be required. If cranes and rigging are involved, a rigger's liability policy with liability limits of \$20,000,000 is required in addition to an inland marine policy covering the value of the contents being moved.

01000S01- Special Conditions - General Contractor

41.2.1.1 The limits of liability shall not be less than \$1,000,000 each occurrence combined single limits for bodily injury and property damage. If split limits are used, they shall not be less than \$1,000,000 for each person and each occurrence and \$1,000,000 for property damage.

41.2.2 Comprehensive Automobile Liability Insurance. Policy limits shall not be less than \$1,000,000 for combined single limits for bodily injury and property damage for each occurrence. As an alternative, split limits of not less than \$1,000,000 for bodily injury and \$1,000,000 for property damage for each occurrence shall be maintained.

41.2.3 Excess or Umbrella Liability Insurance. This policy shall have a minimum of \$100,000,000 combined single limits for bodily injury and property damage for each occurrence in excess of the applicable limits in the primary policies.

41.2.4 Workers' Compensation - Statutory Requirements (Kentucky)

41.2.5 Cyber Liability. Policy limits shall not be less than \$1,000,000 for combined single limits.

ARTICLE 42 KEY ACCESS

42.1 If Construction Cores are NOT utilized, then one set of keys for access to the renovation project area will be provided to the General Contractor by the University's Project Manager. The General Contractor assumes responsibility for the safekeeping of the key(s) and its use. When leaving the renovation area all doors must be secured.

42.2 All keys must be returned to the University's Project Manager upon completion of project work as one of the requirements for Final Payment. Failure to return the keys may require re-keying of all doors in the work area up to and including the entire building if master keys are issued. The cost of re-keying of the door(s) accessed by the key(s) will be subtracted from the remaining contract dollars including contract retainage.

42.3 All lost or stolen keys must be reported immediately to the University's Project Manager.

ARTICLE 43 CEILING CLEARANCE

43.1 Work above ceiling: All work above an area with lay-in ceiling must be coordinated and installed so there is a minimum of 4" between the top of the ceiling grid runners and bottom of the installation. Installation shall not obstruct equipment access space or equipment removal space. Also, conduit and pipe attached to the wall must be above the 4" minimum level.

43.2 Coordination Between Trades: Request and examine all drawings and specifications pertaining to the construction before installing above ceiling work. Cooperate with all other contractors in locating piping, ductwork, conduit, openings, chases, and equipment in order to avoid conflict with any other contractor's work. Give special attention to points where ducts or piping must cross other ducts and piping, and where ducts, piping and conduit must fit into the walls and columns. Make known to other trades intended positioning of materials and intended order of work. Determine intended position of work of other trades and intended order of installation.

01000S01- Special Conditions - General Contractor

ARTICLE 44 METAL ANCHORS

44.1 All anchoring devices utilized to secure materials to the building shall be metal. Plastic or plastic expansion components shall not be used. This shall include all fasteners for mechanical/electrical hangers.

ARTICLE 45 CONTRACTOR/SUPERINTENDENT EXPERIENCE

45.1 For those projects impacting patient care the Construction Manager and Superintendent are required to have a minimum of five (5) years of construction experience in the past 10 years with projects involving patient care areas.